

SECTION 02000  
GENERAL SPECIFICATION FOR SITEWORK

PART 1 - GENERAL

1.1 DESCRIPTIVE

- A. Work included: Site Specification are listed on Civil Sheets, Prepared by DMPR, Inc. 1905 East Colonial Drive. Orlando, FL. 32853. Phone (407)896-0594 Fax (407) 896-4836. Project Manager- John Kelly.

2.2 REPLACEMENTS

- A. In the event of demolition of items not so scheduled to be demolished, promptly replace such items to the approval of the Owner or Utility Owner and at no additional cost to the Owner.

2.3 PROTECTION OF PERSONS AND PROPERTY

1. Barricade open depressions and holes occurring as part of this work, and post warning lights on property adjacent to or with public access.
2. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and Other hazards created by operations.
3. All work shall conform to OSHA Regulations

2.4 RELATED DOCUMENTS

- A. Geotechnical Engineering Study Attached at end of section.

2.5 QUALITY ASSURANCE

- A. Field Engineering: Provide the services of a Professional Engineer or Land Surveyor registered in the State of Florida to establish all vertical and horizontal controls required for layout of the work and for preparation of a certified survey showing recorded finish elevations and dimensions upon completion of site preparation and earthwork.
- B. A testing laboratory, retained by the Owner will make such tests as are deemed necessary by the Owner's Representative to verify the quality of the materials and the work. Schedule work so as to permit a reasonable time for testing fill compaction before placing succeeding lifts and keep the laboratory informed of progress.

END OF SECTION  
SECTION 02000  
GENERAL SPECIFICATION FOR SITEWORK