

SECTION 06150
CARPENTRY

PART 1 - GENERAL

1.1 DESCRIPTION

- A. Work included: Provide wood, fasteners, and other items required, and perform carpentry for the construction shown on the Drawings, as specified herein, and as needed for a complete and proper installation.
 - 1. Miscellaneous wood framing and blocking.
 - 2. Miscellaneous furring.

- B. Related work:
 - 1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions, and Sections in Division 1 of these Specifications.
 - 2. Section 06200: Finish Carpentry.

1.2 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.3 REQUIREMENTS OF REGULATORY AGENCIES

- A. Fire Retardant Treated Wood: Treat wood required by Building Codes to be treated and wood shown as "Fire Retardant Treated Wood".

- B. Comply with the requirement of the State, County, City and other required Building Codes and submit all necessary applications and Certificates to the Building Department for approval.

PART 2 - PRODUCTS

2.1 PLYWOOD

- A. CDX roof and inside of soffit, use grade stamped DEPA, grade c/d Plugged, or equal as approved in advance by the Owner.

SECTION 06150-2
CARPENTRY

2.2 OTHER MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation as selected by the Contractor, subject to the approval of the Owner.
- B. Preservative Treated Wood:
 - 1. Wood in contact with concrete or masonry and wood adjacent to water proofing and flashing.
 - 2. Treatment: Pressure treat in a closed retort by vacuum-pressure process in compliance with AWPA C-2 for lumber and AWPA C-9 for plywood.

PART 3 - EXECUTION

3.1 SURFACE CONDITIONS

- A. Examine the areas and conditions under which work of this Section will be performed. Correct conditions detrimental to timely and proper completion of the Work. Do not proceed until satisfactory conditions are corrected.

3.2 WORKMANSHIP

- A. Install items straight, true, level, plumb, and securely anchored into position.
- B. Where blocking or backing is required, coordinate as necessary with other trades to assure placement of required blocking and backing in a timely manner.

END OF SECTION
CARPENTRY
06150-2