

SECTION 06200  
FINISH CARPENTRY

PART 1 – GENERAL

1.1 DESCRIPTION

- A. Work included: Install wood trim and other items not specifically described as being installed under other Sections of these Specifications.
1. Exterior Paneling: Honey Oak manufactured by Georgia Pacific over and/or above Walk in Beer Cooler, Wine Chiller and Humidor.
  2. EXTERIOR- Base at flooring for the Walk in Beer Cooler, Wine Chiller and Humidor shall be clear stain grade colonial base, stained with Fruitwood, and finished with two coats of polyurethane. Chasing at Wine Chiller and Humidor to be stained with Fruitwood, and finished with two coats of polyurethane.
  3. INTERIOR- Wine Chiller and Humidor interior shall be rough saw cedar. Trim as specified on plans. All wood to remain unfinished.
- B. Related work:
1. Documents affecting work of this Section include, but are not necessarily limited to, General Conditions, Supplementary Conditions, and Sections in Division I of these Specifications.

1.2 QUALITY ASSURANCE

- A. Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary crafts and who are completely familiar with the specified requirements and the methods needed for proper performance of the work of this Section.

1.3 SUBMITTALS

- A. Owner will supply the awarded Contractor shelving brackets and ticket molding to be installed in Wine Chiller and Humidor.
- B. Contractor to submit samples of Rough Sawn Cedar and paneling to Owner for approval.

1.4 PRODUCT HANDLING

- A. Comply with pertinent provisions of Section 01640.

FINISH CARPENTRY  
SECTION 06200-2

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Provide other materials, not specifically described but required for a complete and proper installation, as selected by the Contractor subject to the approval of the Owner.
- B. All Finish molding shall be first grade. All molding shall receive two coats of stain and one coat of varnish prior to installation.
- C. Provide all wood free of any significant defects or deviations from Grade standards.
- D. Jointing shall be made to conceal shrinkage. Make saw cuts straight and clean. Make tight fits without gaps. Use maximum size material to keep number of joints to a minimum. Glue all joints.
- E. Finishing, where sanding is required, sand with grain to totally smooth unblemished surface. Set finish nails before sanding or painting.
- F. Supports for Shelves in Humidor to start 12” from inside corner and be equally spaced up to 36” O.C. Wine Chiller to start 12” from inside corner and to be equally spaced up to 24” O.C.
- G. Owner shall supply Supports for shelves and ticket molding for Humidor and Wine Chiller. Contractor shall provide to Owner quantities of shelf supports and lengths of ticket molding. TICKET MOLDING SHALL BE GLUED PRIOR TO NAILING.
- H. NO FACE NAILING OF TOUNGE AND GROOVE... NO BUTT JOINTS...

END OF SECTION  
FINISH CARPENTRY  
06200-2