



1 Floor Plan  
Scale 1/8"=1'-0"

LEGEND	
SYMBOL	DESCRIPTION
[Symbol]	CANOPY ACCESS HATCH REF: A141-4
[Symbol]	MAXIMUM EGRESS PATH
[Symbol]	DOOR NUMBER RE. SHT. A601
[Symbol]	STOREFRONT WINDOW SYSTEM RE. SHT. A601
[Symbol]	WALL TYPE, RE. SHT. A401
[Symbol]	ENLARGED DETAIL SEE REFERENCED SHEET

Finish Schedule			
FLOOR MATERIAL	WALL BASE MATERIAL	WALL MATERIAL	CEILING MATERIAL
A SEALED CONCRETE	1 NONE	A PAINT READY	1 ACOUSTICAL LAY-IN TILE
B VCT TILE	2 VINYL	B ENAMEL PAINTED GYPSUM BOARD	2 PAINTED GYPSUM BOARD
C CERAMIC TILE	3 CERAMIC	C CERAMIC TILE	3 NONE
D NOT USED	4 NOT USED	D ENAMEL PAINTED CONC. BLOCK	4 NOT USED

1. GENERAL

- SCOPE: FURNISH ALL LABOR, MATERIALS AND EQUIPMENT NECESSARY TO COMPLETE THE APPLICATION OF SOIL POISONING FOR THE TERMITE CONTROLS SPECIFIED HEREIN.
- CONTRACTOR'S QUALIFICATIONS: APPLICATOR SHALL BE LICENSED IN THE STATE WHERE THE PROJECT IS LOCATED AND SHALL BE A NATIONALLY KNOWN COMPANY.
- GUARANTEE:
  - TERMITE TREATMENT PROTECTION SHALL BE GUARANTEED FOR A PERIOD OF FIVE (5) YEARS AGAINST TERMITE INFESTATION. GUARANTEE SHALL INCLUDE ANY YEARLY RENEWAL COSTS. REPAIRS FOR TERMITE DAMAGE PAID BY TERMITE COMPANY.
  - AT THE OWNERS OPTION, AT THE TERMINATION OF THE GUARANTEE, AN EXTENSION RENEWAL OF INSPECTION AND SERVICE TREATMENT SHALL BE MADE AVAILABLE TO THE OWNER.

2. PRODUCTS

- SOIL POISONS APPLIED TO THE DESIGNATED AREAS SHALL BE WATER BASED EMULSIONS CONTAINING TOXICANTS IN EITHER OF THE TWO COMBINATIONS LISTED BELOW. EACH TOXICANT SHALL BE IN THE CONCENTRATION (BY WEIGHT).
  - IMIDACLOPRID (5%-10%) AND DIELDRIN (0.5%)
  - PERMETHRIN (1.0%) AND HEPTACHLOR (0.16%)

3. EXECUTION

RESTRICTIONS: DO NOT APPLY SOIL TREATMENT SOLUTION UNTIL EXCAVATING, FILING AND OR GRADING OPERATIONS ARE COMPLETED, EXCEPT AS OTHERWISE REQUIRED IN CONSTRUCTION OPERATIONS TO ENSURE PENETRATION; DO NOT APPLY SOIL TREATMENT TO EXCESSIVELY WET SOIL OR DURING INCLEMENT WEATHER.

SURFACE PREPARATION: REMOVE FOREIGN MATTER WHICH COULD DECREASE EFFECTIVENESS OF TREATMENT ON AREAS TO BE TREATED. LOOSEN, RAKE AND LEVEL SOIL TO BE TREATED, EXCEPT PREVIOUSLY COMPACTED AREAS UNDER SLABS AND FOUNDATIONS. TOXICANT MAY APPLY BEFORE PLACEMENT OF COMPACTED FILL UNDER SLABS, IF ACCEPTABLE TO THE ARCHITECT.

APPLICATION RATES: APPLY SOIL TREATMENT SOLUTION AS FOLLOWS: WITHIN BUILDING AREA, WITH OR WITHOUT SLABS ON-GRADE, AT THE RATE OF 1.5 GAL. PER 10 SQ. FT. UNDER FOUNDATIONS AND FOOTINGS, INCLUDING HORIZONTAL AND VERTICAL SURFACES OF EXCAVATIONS, AT THE RATE OF 1 GAL. PER 10 SQ. FT. OUTSIDE BUILDING PERIMETER IN A STRIP AT LEAST 2' WIDE AND UNDER PORCHES, AREAWAY, APRONS, WALKS, PADS, STAIR LANDINGS OR PAVED EXTENSIONS, AT A RATE OF 1 GAL. PER 5 SQ. FT.. ALLOW NOT LESS THAN 12 HOURS FOR DRYING AFTER APPLICATION, BEFORE BEGINNING CONCRETE PLACEMENT OR OTHER CONSTRUCTION ACTIVITIES.

POST SIGNS IN THE AREAS OF APPLICATION WARNING WORKERS THAT SOIL POISONING HAS BEEN APPLIED. REMOVE SIGNS WHEN AREAS ARE COVERED WITH OTHER CONSTRUCTION.

REAPPLY SOIL TREATMENT SOLUTION TO AREA DISTURBED BY SUBSEQUENT EXCAVATION OR OTHER CONSTRUCTION ACTIVITIES FOLLOWING APPLICATION.

- POST A PERMANENT SIGN POSTED BESIDE THE ELECTRICAL PANEL IDENTIFYING THE TERMITE TREATMENT PROVIDER AND NEED FOR RE-INSPECTION AND TREATMENT CONTRACT RENEWAL TO BE PROVIDED.
- IRRIGATION / SPRINKLER SYSTEMS INCLUDING ALL RISERS AND SPRAY HEADS SHALL NOT BE INSTALLED WITHIN 1'-0" OF THE BUILDING WALLS.
- PROVIDE A MINIMUM OF 6" BETWEEN WALL COVERINGS AND FINAL EARTH GRADE TO ALLOW FOR INFESTATION INSPECTION.
- BOXED AREAS IN CONCRETE FLOORS FOR SUBSEQUENT INSTALLATION OF TRAPS, ETC., SHALL BE MADE WITH PERMANENT METAL OR PLASTIC FORMS OF A SIZE AND DEPTH THAT WILL ELIMINATE THE DISTURBANCE OF SOIL AFTER THE INITIAL TREATMENT.
- A MINIMUM OF 10 MIL VAPOR RETARDER MUST BE INSTALLED TO PROTECT AGAINST RAINFALL DILUTION. IF RAINFALL OCCURS BEFORE VAPOR RETARDER PLACEMENT, RETREAT AS REQUIRED.
- AFTER ALL WORK IS COMPLETED, LOOSE WOOD AND FILL MUST BE REMOVED FROM BELOW AND WITHIN 1'-0" OF THE BUILDING. THIS INCLUDES ALL GRADE STAKES, TUB TRAP BOXES, FORMS, SHORING OR OTHER CELLULOSE CONTAINING MATERIAL.
- A CERTIFICATE OF COMPLIANCE MUST BE ISSUED TO THE BUILDING DEPARTMENT BY A LICENSED PEST CONTROL COMPANY BEFORE A CERTIFICATE OF OCCUPANCY WILL BE ISSUED.
- NO WOOD, VEGETATION, STUMPS, CARDBOARD, TRASH, ETC., SHALL BE BURIED WITHIN 15'-0" OF ANY BUILDING OR OR PROPOSED BUILDING.

PROJECT NO.	DATE	DRAWN	CHECKED
200650	08/28/08	JEI	JEI