

OWNER FURNISHED ITEMS

SECTION 01018

PART I GENERAL

1.1 SECTION INCLUDES

- A. Provide coordination of the installation of the equipment or system, identified within this Section, with other trades. Problems noted shall be brought to the attention of the Architect. This notification must be submitted in writing and no claims for additional work shall be considered unless the request for clarification has been timely initiated by the Contractor.

1.2 EQUIPMENT SCHEDULE

- A. The equipment schedule is a listing of equipment to be furnished for this project.

1.3 SUBMITTALS

- A. Manufacturer's shop drawings or installation drawings for certain equipment or systems will be furnished by the Owner. The information on these drawings shall be transferred to the Record Documents.
- B. Vendor drawings have been provided for contractor convenience and coordination within the drawing sets. Upon receipt, Contractor to advise Architect and Owner of any discrepancies that exist between the requirements of the Contract Documents and the vendor drawings.
- C. Review cut sheets provided by the owner's equipment consultant. Become familiar with the specific requirements of each piece of equipment; including the need for backing/in-wall blocking, power supply, conduit, plumbing connections and structural supports.
- D. Contractor is responsible to coordinate in a timely manner with his subcontractors all connection data such as electrical plug configurations, pipe sizing, etc.

1.4 OWNER FURNISHED, CONTRACTOR INSTALLED ITEMS

- A. (As needed.)

1.5 OWNER FURNISHED, CONTRACTOR ROUGH-IN, OWNER INSTALLED ITEMS

- A. (As needed)

1.6 OWNER FURNISHED, OWNER INSTALLED ITEMS

- A. Contractor has no Responsibility: for these items, other than protecting items from damage that may be installed by owner following substantial completion.

PART II PRODUCTS
(Not Applicable)

PART III EXECUTION

3.1 INSTALLATION

- A. Manufacturer's Supervision: Uncrating, assembly of equipment components shipped loose, installation and hook-up of equipment shall be supervised by manufacturer or manufacturer's authorized representative in accordance with manufacturer's installation directions and reviewed insulation drawings.
- B. Mechanical Stub-outs: Proper trade to temporarily terminate supply pipe lines at shut-off valves near respective items of equipment at locations indicated on approved manufacturer's installation drawings.
- C. Electrical Stub-outs: Proper trade shall temporarily terminate electrical work at locations indicated on reviewed manufacturer's installation drawings. Equipment supplier shall supervise connecting his equipment thereto.
- D. Workmanship: Install equipment plumb, true, with horizontal lines level, joints tight and units rigidly secured in place.
- E. Testing and Adjustments: Equipment supplier shall be responsible for final installation of each item including all corrections, repairs, test, cleaning, calibration, regulation and adjustments necessary so that each item can be used as intended and at time established by schedule of Work.
- F. Cleaning: After assembly, installation and hook-ups are complete, clean exposed exterior and interior surfaces and leave in satisfactory condition.

3.2 START-UP AND INSTRUCTIONAL PERIOD

- A. Provide start-up service and instruct owner's personnel in operation, adjustment, care and maintenance equipment for up to one week.

END OF SECTION